




Remedial Investigation/Feasibility Study Report for IR Sites 14 and 15

Glenna Clark
Remedial Project Manager
NAVFAC Southwest Division

October 1, 2002








Site 14 – Former Fire Training Area

- Fire training school through 1987
- Burning of waste fuel occurred within bermed area, unburned fuel captured in sump
- Building 528 (maintenance shop)
- CAA-2
- GAP 9
- GAP 11







Current Status - Site 14


- CAA-2 recommending no further action under the TPH Program
- TPH is not a chemical of concern
- Removal Action for dioxins in berm/sump area completed.
 No further action is recommended.
- No significant risk from soil.
- Groundwater is recommended for remedial action. 1,1dichloroethane (DCA), 1,2-dichloroethene (DCE), trichloroethene (TCE), and vinyl chloride (VC) exceed the MCL





Site 15 – Former Transformer Storage Area

- Area used for storage of electrical equipment, oil-filled transformers, and machinery
- A non-time critical removal action was conducted in 1995 to excavate surface soil contaminated with PCBs and lead.
- Analytical data from additional soil sampling conducted in 2001 as part of the Data Gap Sampling event failed to verify significant lead and PCB concentrations. As a result, a planned removal action was canceled by the BCT.







Current Status – Site 15

- Removal Action for lead and PCBs is complete no further action
- No significant soil or groundwater risk
- Entire site recommended for no further action





Site 14 Feasibility Study

Remedial Action Objective: Prevent human ingestion of groundwater containing VOCs at concentrations above the state MCLs.



ALAMEDA POINT





General Response Actions

No Action No remedial measures will be taken at the

site

Land Use Controls Non-engineered instruments such as

administrative and/or legal controls that

minimize the potential for human exposure

to contamination by limiting land or

resource use

Active Remediation Engineering technologies that minimize or

eliminate the potential exposure of human

and ecological receptors to contamination

by reducing contaminant toxicity, volume,

or mobility through treatment or

containment





Schedule

Draft Remedial Investigation

Report

August 15, 2002

Draft Feasibility Study Report

October 15, 2002

Draft Proposed Plan

March 15, 2003

Draft ROD

September 30, 2003